

<b>Title</b>	<b>Install and finish decorative exterior mouldings to Proprietary Plaster Cladding Systems on site</b>		
<b>Level</b>	<b>3</b>	<b>Credits</b>	<b>8</b>

<b>Purpose</b>	People credited with this unit are able to: identify and order decorative mouldings in accordance with job specifications; prepare and install decorative mouldings on site; and complete joint finishing and edge sealing of decorative mouldings on site.
----------------	---

<b>Classification</b>	Construction Trades > Proprietary Plaster Cladding Systems
-----------------------	--

<b>Available grade</b>	Achieved
------------------------	----------

### Guidance Information

#### 1 Definitions

*On site* refers to a wide range of building and construction environments within which the Proprietary Plaster Cladding Systems trade skills are applied.

*Specifications* refers to documented instructions (oral, written, graphic) and may include any of the following: manufacturer's specifications, recommendations or technical data sheets; material specifications; specifications from a specialist source such as an architect, designer, engineer or a supervisor; site or work specific requirements.

*Work site practice* refers to the documented procedures specific to a work site, which set out the standard and required practices of that work site.

#### 2 Legislation, regulations, codes and standards relevant to this unit standard include:

Health and Safety in Employment Act 1992;

Health and Safety in Employment Regulations 1995;

Resource Management Act 1991;

Hazardous Substances and New Organisms Act 1996; Building Act 2004;

New Zealand Standards, NZS 4218:2004 *Energy efficiency – Small building envelope* and NZS 3604:1999 *Timber Framed Buildings*, available from Standards NZ (<http://www.standards.co.nz>);

New Zealand Building Code;

Territorial Authorities' building regulations.

#### 3 Credit for this unit standard indicates compliance with industry practice. *Industry practice* refers to the ability to demonstrate knowledge and skills that reflect the productivity, uniformity, finish quality and material economies currently accepted within industry.

---

## Outcomes and performance criteria

### Outcome 1

Identify and order decorative mouldings in accordance with job specifications.

Range designer's and owner's requirements.

### Performance criteria

- 1.1 Work to be done is determined from plans, working drawings and specifications in terms of types of decorative mouldings, materials and workmanship to be used.
- 1.2 The range of moulding options available is identified and their applications in different situations are described.
- Range two of – uncoated polystyrene, polyurethane, premeshed, precoated.
- 1.3 The sizing, measuring and ordering process for mouldings is identified and described in relation to job specifications.
- 1.4 The ordering, receipt, checking, and site storage of decorative mouldings and fixings are undertaken in accordance with job specifications and work site practice.
- Range confirmation of delivered materials, return or replacement of defective materials, use of appropriate handling and storage methods to prevent damage.

### Outcome 2

Prepare and install decorative mouldings on site.

### Performance criteria

- 2.1 Surface area layout for decorative mouldings is prepared and confirmed against plans, working drawings and job specifications.
- Range tools used include two of – string lines, plumb lines, level lines, chalk lines, laserlines.
- 2.2 Actions to be taken in the event that the fixing surfaces are not in accordance with a plan, specifications, or work site practice, are described.
- Range cleaning, levelling, straightening

- 2.3 Cuts and mitres for decorative mouldings are completed to meet manufacturer's instructions, job specifications and work site practice.

Range tools used – hand saw, power saw.

- 2.4 Fixing methods used with decorative mouldings are identified and confirmed against the manufacturer's instructions and job specifications.

Range two of – mechanical fasteners, adhesives, modified plaster.

- 2.5 Decorative mouldings are installed and fixed in accordance with manufacturer's instructions and job specifications.

### Outcome 3

Complete joint finishing and edge sealing of decorative mouldings on site.

Range two of – plastering, mesh reinforcing, sealants.

### Performance criteria

- 3.1 Joint finishing of decorative mouldings is completed in accordance with manufacturer's instructions and without damage.
- 3.2 Edge sealing of decorative mouldings is completed in accordance with manufacturer's instructions and without damage.

**This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.**

#### Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	23 June 2000	31 December 2024
Review	2	24 January 2006	31 December 2024
Review	3	26 January 2007	31 December 2024
Review	4	30 June 2022	31 December 2024

<b>Consent and Moderation Requirements (CMR) reference</b>	0048
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.