

<b>Title</b>	<b>Cast fibrous plaster cornices</b>		
<b>Level</b>	<b>3</b>	<b>Credits</b>	<b>4</b>

<b>Purpose</b>	People credited with this unit standard are able to: cast fibrous plaster cornices; run fibrous plaster cornices; and clean up after work is completed.
----------------	---

<b>Classification</b>	Construction Trades > Fibrous Plaster
-----------------------	---------------------------------------

<b>Available grade</b>	Achieved
------------------------	----------

---

### Guidance Information

- 1 Credit for this unit standard can be achieved on site through a registered assessor, or off site with an accredited training provider.
- 2 *Specifications* refers to documented instructions (oral, written, graphic) and may include any of the following: manufacturer's specifications or recommendations; material specifications; specifications from a specialist source such as an architect, designer, engineer or a supervisor; site or work specific requirements.  
*Green cornices* means freshly cast cornices of fibrous plaster that have yet to be dried.  
*Work site practice* refers to the practices generally acknowledged by the industry as being acceptable, and to the documented procedures which set out the standard and required practices of the work site at which this unit standard is being assessed.
- 3 All work practices must comply with the following:  
Health and Safety in Employment Act 1992 and Health and Safety in Employment Regulations 1995; Resource Management Act 1991; Building Act 2004;  
AS/NZS 2589.2:1997 *Gypsum linings in residential and light commercial construction – Application and finishing – Fibre reinforced gypsum plaster*, available from Standards NZ (<http://www.standards.co.nz>);  
New Zealand Building Code.

---

### Outcomes and performance criteria

#### Outcome 1

Cast fibrous plaster cornices.

#### Performance criteria

- 1.1 Moulds are prepared in accordance with manufacturer's specifications.

- 1.2 Plaster is mixed, and cornices are cast and reinforced in accordance with manufacturer's specifications.
- 1.3 Green cornices are dried and stored in accordance with manufacturer's specifications.

## Outcome 2

Run fibrous plaster cornices.

### Performance criteria

- 2.1 Templates and guides are prepared and set up in accordance with work site practice.
- 2.2 Plaster is mixed, reinforcing is placed and cornices are run in straight lengths to conform to manufacturer's specifications.
- 2.3 Green cornices are dried and stored in accordance with manufacturer's specifications.

## Outcome 3

Clean up after work is completed.

### Performance criteria

- 3.1 Tools and plant are maintained, cleaned and stored in accordance with site practice.
- 3.2 Waste material is disposed of and workplace is cleaned in accordance with site practice.

**This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.**

#### Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	18 January 1996	31 December 2024
Revision	2	5 July 1999	31 December 2024
Review	3	29 August 2000	31 December 2024
Revision	4	18 May 2005	31 December 2024
Review	5	20 April 2006	31 December 2024
Review	6	26 May 2022	31 December 2024

<b>Consent and Moderation Requirements (CMR) reference</b>	0048
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.

This unit standard is expiring