

<b>Title</b>	<b>Cast straight fibrous plaster decorative mouldings</b>		
<b>Level</b>	<b>3</b>	<b>Credits</b>	<b>4</b>

<b>Purpose</b>	People credited with this unit standard are able to: cast fibrous plaster decorative mouldings; run fibrous plaster mouldings; and clean up after work is completed.
----------------	--

<b>Classification</b>	Construction Trades > Fibrous Plaster
-----------------------	---------------------------------------

<b>Available grade</b>	Achieved
------------------------	----------

---

### Guidance Information

- 1 Credit for this unit standard can be achieved on site through a registered assessor, or off site with an accredited training provider.
- 2 Definitions  
*Specifications* refers to documented instructions (oral, written, graphic) and may include any of the following: manufacturer's specifications or recommendations; material specifications; specifications from a specialist source such as an architect, designer, engineer or a supervisor; site or work specific requirements.  
*Green mouldings* means freshly cast mouldings of fibrous plaster that have yet to be dried.
- 3 All work practices must comply with the following:  
Health and Safety in Employment Act 1992 and Health and Safety in Employment Regulations 1995; Resource Management Act 1991; Building Act 2004;  
AS/NZS 2589.2:1997 *Gypsum linings in residential and light commercial construction – Application and finishing – Fibre reinforced gypsum plaster*, available from Standards NZ (<http://www.standards.co.nz>);  
New Zealand Building Code.

---

### Outcomes and performance criteria

#### Outcome 1

Cast fibrous plaster decorative mouldings.

#### Performance criteria

- 1.1 Moulds are prepared in accordance with manufacturer's specifications.
- 1.2 Plaster is mixed, and mouldings are cast and reinforced in accordance with manufacturer's specifications.

- 1.3 Green mouldings are dried and stored in accordance with manufacturer's specifications.

## Outcome 2

Run fibrous plaster mouldings.

### Performance criteria

- 2.1 Templates and guides are set up in accordance with manufacturer's specifications.
- 2.2 Plaster is mixed, reinforcing is placed and mouldings are run in straight lengths in accordance with manufacturer's specifications.
- 2.3 Green mouldings are dried and stored in accordance with manufacturer's specifications.
- 2.4 All operations are completed without damage to the workplace, tools or plant.

## Outcome 3

Clean up after work is completed.

### Performance criteria

- 3.1 Tools and plant are maintained, cleaned and stored in accordance with site practice.
- 3.2 Waste material is disposed of and workplace is cleaned in accordance with site practice.

**This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.**

### Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	18 January 1996	31 December 2024
Revision	2	5 July 1999	31 December 2024
Review	3	29 August 2000	31 December 2024
Revision	4	18 May 2005	31 December 2024
Review	5	20 April 2006	31 December 2024
Review	6	26 May 2022	31 December 2024

<b>Consent and Moderation Requirements (CMR) reference</b>	0048
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.