Title	Install splashbacks and mirrors		
Level	4	Credits	10

Purpose	This unit standard is for experienced people working in the glazing industry.
	People credited with this unit standard are able to prepare to install and install splashbacks and mirrors.

Classification	Glass and Glazing > Flat Glass	

Available grade	Achieved		
-----------------	----------	--	--

Guidance Information

1 Definitions

Worksite requirements – refer to instructions to staff on policy and procedures which are documented in memo or manual format and are available in the workplace. These requirements include – company specifications and procedures, work instructions, manufacturer's specifications, product quality specifications, legislative requirements.

Splashbacks - splashbacks, glass wall cladding.

- 2 Legislation and standards relevant to this unit standard include Building Act 2004, Health and Safety in Employment Act 1992, New Zealand Standard (NZS) 4223.3:1999 Glazing in buildings - Human impact safety requirements, available at http://www.standards.co.nz.
- 3 Range Evidence is required of two splashbacks and two mirrors.

Outcomes and performance criteria

Outcome 1

Prepare to install splashbacks and mirrors.

Performance criteria

1.1 Customer's requirements are confirmed before work begins in accordance with worksite requirements.

Range requirements include – work required, fixing method, material and quantities required, location of job, site accessibility, location of services.

- 1.2 Splashbacks and mirrors for installation are checked for faults before work commences in accordance with worksite requirements.
 - Range faults include scratches, silver faults, edge damage, glass faults, edge seal damage.
- 1.3 All necessary equipment, tools, and installation materials are checked and assembled before work begins in accordance with worksite requirements.
- 1.4 Installation plan is prepared in accordance with the job specifications and customer and worksite requirements.

Outcome 2

Install splashbacks and mirrors.

Performance criteria

- 2.1 Hidden services are located before installation in accordance with worksite requirements.
 - Range services include electrical, plumbing.
- 2.2 Wall is checked for flatness and squareness in accordance with worksite requirements.
- 2.3 Adhesives selected are compatible with splashback or mirror backing and mounting surface and are used in accordance with worksite requirements.
- 2.4 Methods for fixing splashbacks and mirrors to walls are described in accordance with the job specifications and worksite requirements.
 - Range methods include adhesive, screws, tape, metal channelling, mounts, frames, mirror pads, cutting on site.
- 2.5 Splashbacks and mirrors are fixed to wall and installation is square, plumb, and secure in accordance with the job specifications and worksite requirements.
- 2.6 Drainage and/or freely ventilated airspace between the splashback or mirror and wall is provided to meet the job specifications and worksite requirements.
- 2.7 Operations are completed without injury to personnel or damage to products and equipment in accordance with the job specifications and worksite requirements.
- 2.8 Installation is cleaned and work area is clear and cleaned in accordance with worksite requirements.
- 2.9 Customer is advised of any relevant maintenance requirements in accordance with worksite requirements.

This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.

Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	11 June 1995	31 December 2013
Revision	2	5 February 1997	31 December 2013
Revision	3	20 December 1999	31 December 2013
Review	4	27 April 2004	31 December 2013
Review	5	21 May 2010	31 December 2017
Review	6	18 June 2015	31 December 2024
Review	7	24 November 2022	31 December 2024

Consent and Moderation Requirements (CMR) reference	0048
---	------

This CMR can be accessed at http://www.nzqa.govt.nz/framework/search/index.do.