| Title | Install rocks as features for landscape work | | |
|-------|--|---------|---|
| Level | 4 | Credits | 5 |

| Purpose | People credited with this unit standard are able to: describe common types and sources of rock used as landscape features; and source and order materials required for a natural rock feature, and place natural rock as a landscape feature. |
|---------|--|
| | Tock realure, and place halural fock as a landscape realure. |

| Classification | Horticulture > Landscape |
|-----------------|--------------------------|
| | |
| Available grade | Achieved |

Guidance Information

- 1 Legislation relevant to this unit standard includes but is not limited to:
 - Health and Safety at Work Act 2015;
 - Resource Management Act 1991; and any subsequent amendments.
- 2 Definition

Workplace procedures refer to the procedures and standards set by the client or employing organisation for rock installation and must be consistent with manufacturers guidelines and plans and specifications.

- 3 Any work carried out in playground areas must comply with the New Zealand Standard: NZS 5828:2004, *Playground equipment and surfacing,* available from http://www.standards.govt.nz.
- 4 All evidence presented in this unit standard must be in accordance with workplace procedures.

Outcomes and performance criteria

Outcome 1

Describe common types and sources of rock used as landscape features.

Performance criteria

1.1 Describe the characteristics of common types of natural rock used as landscape features.

Range evidence of four common types of natural rock is required; common name, geological name, sources, general characteristics.

Outcome 2

Source and order materials required for a natural rock feature, and place natural rock as a landscape feature.

Range features may include but are not limited to – sculptural rock features, rockeries, gabian baskets evidence for two separate features is required.

Performance criteria

- 2.1 Source and order materials required for a rock feature.
- 2.2 Place and secure rock elements while maintaining communication with mechanical operator and ground staff.
- 2.3 Check and confirm stability of installed rock before lifting or removing support attachments.
- 2.4 Install or use safety warnings during construction when work is accessible to the public.
- 2.5 Select, prepare, and use the appropriate hand and power tools, and equipment for the job.
- 2.6 Remove surplus material and reinstate the site on completion of the job.
- 2.7 Work safely around other people and machinery on site.

| Planned review date | 31 December 2026 |
|---------------------|------------------|
|---------------------|------------------|

Status information and last date for assessment for superseded versions

| Process | Version | Date | Last Date for Assessment |
|--------------|---------|-------------------|--------------------------|
| Registration | 1 | 11 January 1994 | 31 December 2019 |
| Review | 2 | 28 November 1997 | 31 December 2019 |
| Revision | 3 | 19 July 2001 | 31 December 2019 |
| Revision | 4 | 13 March 2003 | 31 December 2019 |
| Review | 5 | 25 September 2006 | 31 December 2019 |
| Review | 6 | 29 March 2018 | 31 December 2025 |
| Review | 7 | 24 March 2022 | N/A |

| Consent and Moderation Requirements (CMR) reference | 0052 | |
|--|------|--|
| This CMR can be accessed at http://www.nzga.govt.nz/framework/search/index.do. | | |

Comments on this unit standard

Please contact Muka Tangata - People, Food and Fibre Workforce Development Council <u>qualifications@mukatangata.nz</u> if you wish to suggest changes to the content of this unit standard.