Level 4 Credits 6	Title	Dismantle electricity networ	k lines and st	ructures
	Level	4	Credits	6

Purpose	People credited with this unit standard are able to dismantle electricity network lines and structures.	
Classification	Electricity Supply > Electricity Supply - Distribution Networks	
Available grade	Achieved	
Prerequisites	Unit 10509, Climb and work on electricity network structures; and Unit 28112, Operate and store machinery, plant, and equipment in an electricity network environment; or demonstrate equivalent knowledge and skills.	

Guidance Information

- 1 Evidence presented for assessment against this unit standard must be consistent with safe working practices and be in accordance with applicable industry and legislative requirements.
- 2 Legislation, regulations and/or industry standards relevant to this unit standard include but are not limited to the current version of the Health and Safety at Work Act 2015; Electricity Act 1992; Electricity (Safety) Regulations 2010; and any subsequent amendments and replacements; Electricity supply industry codes of practice and documented enterprise procedures, including Safety Manual Electricity Industry (SM-EI) (2015) Wellington: Electricity Engineers' Association available from www.eea.co.nz.
- 3 Definitions
 - Asset owner refers to a participant who owns or operates assets used for generating or conveying electricity.
 - *Industry requirements* include all asset owner requirements; manufacturers' specifications; and enterprise requirements which cover the documented workplace policies, procedures, specifications, business, and quality management requirements relevant to the workplace in which assessment is carried out.
- 4 Recommended skills and knowledge: Unit 10508, *Identify electricity systems used in the electricity supply industry* or demonstrate equivalent knowledge and skills.

Outcomes and performance criteria

Outcome 1

Dismantle electricity network lines and structures.

Range poles or towers;

evidence is required for three different locations.

Performance criteria

- 1.1 Scope of work is established, and site is prepared.
- 1.2 Guying is applied and structure is rigged for conductor lowering.
- 1.3 Electricity network lines are disconnected, lowered, and made ready for transport.
- 1.4 Structure is dismantled, disassembled, and bundled ready for transportation.
- 1.5 Electricity network site is reinstated.
- 1.6 Completed work is reported concisely in the required format and filed within the scheduled time-frame.

Planned review date	31 December 2024
---------------------	------------------

Status information and last date for assessment for superseded versions

otatas information and last date for assessment for superscaed versions			
Process	Version	Date	Last Date for Assessment
Registration	1	19 June 1997	31 December 2016
Review	2	27 April 2001	31 December 2016
Review	3	22 October 2003	31 December 2016
Review	4	20 November 2009	31 December 2016
Review	5	20 March 2014	31 December 2021
Review	6	28 November 2019	N/A

Consent and Moderation Requirements (CMR) reference	0120
---	------

This CMR can be accessed at http://www.nzqa.govt.nz/framework/search/index.do.

Comments on this unit standard

Please contact the Connexis - Infrastructure Industry Training Organisation at qualifications@connexis.org.nz if you wish to suggest changes to the content of this unit standard.