Title	Remove and install line hardware and equipment on structures using live line hot stick up to 66kV				
Level	4		Credits	20	
Purpose		People credited with this unit standard are able to remove and install line hardware and equipment using live line hot stick up to 66kV.			
Classification		Electricity Supply > Electricity Supply - Live Work			
Available grade		Achieved			
Prerequisites		Unit 10538, Inspect, test, and clean live line tools and equipment; Unit 10542, Demonstrate knowledge of live line theory and procedures; or demonstrate equivalent knowledge and skills.			

Guidance Information

- 1 Entry into live work is conditional on the trainee meeting the minimum requirements of NZECP 46:2003: *New Zealand Electrical Code of Practice for High Voltage Live Line Work* available at https://worksafe.govt.nz/.
- Evidence presented for assessment against this unit standard must be consistent with safe working practices and be in accordance with applicable legislative and industry requirements.
- 3 Legislation, regulations and/or industry standards relevant to this unit standard include but are not limited to the current version of the Health and Safety at Work Act 2015; Electricity Act 1992; Electricity (Safety) Regulations 2010; and any subsequent amendments and replacements; Electricity supply industry codes of practice and documented enterprise procedures, including Safety Manual Electricity Industry (SM-EI) (2015) Wellington: Electricity Engineers' Association available at www.eea.co.nz.
- 4 Definitions

Asset owner refers to a participant who owns or operates assets used for generating or conveying electricity.

Industry requirements include all asset owner requirements; manufacturers' specifications; and enterprise requirements which may include the documented workplace policies, procedures, specifications, business, and quality management requirements relevant to the workplace in which assessment is carried out.

5 This unit standard includes but is not limited to – conductors, insulators, cross arms, fittings and other components on poles, towers, and other structures.

Outcomes and performance criteria

Outcome 1

Remove and install line hardware and equipment on structures using live line hot stick up to 66kV.

Performance criteria

1.1 Worksite is prepared, and a safe working zone is established.

Range includes – site information, plans, procedures, approvals, tools, equipment, working platforms, communication with affected personnel.

- 1.2 Conductors are displaced and reinstated on intermediate structures and termination structures.
 - Range includes but is not limited to auxiliary arm, tongs, 2x2 block and tackles, hoists.
- 1.3 Line hardware and equipment is replaced, and worksite is reinstated.
 - Range includes insulators, cross arms, fittings, fault indicators, vibration dampers.
- 1.4 Completed work is reported concisely, in the required format and within the scheduled time frame, and existing records are updated.

Planned review date	31 December 2025
---------------------	------------------

Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	19 June 1997	31 December 2022
Review	2	27 April 2001	31 December 2022
Review	3	22 October 2003	31 December 2022
Review	4	18 September 2009	31 December 2022
Revision	5	21 May 2010	31 December 2022
Review	6	27 February 2020	N/A

Consent and Moderation Requirements (CMR) reference	0120
---	------

This CMR can be accessed at http://www.nzqa.govt.nz/framework/search/index.do.

Comments on this unit standard

Please contact Connexis – Infrastructure Industry Training Organisation qualifications@connexis.org.nz if you wish to suggest changes to the content of this unit standard.