Title	Replace and install hardware on structures using live line glove and barrier procedures up to 33kV				
Level	5		Credits	30	
Purpose		People credited with this unit standard are able to replace and install hardware on structures using live line glove and barrier procedures up to 33kV.			
Classification		Electricity Supply > Electricity Supply - Live Work			
Available grade		Achieved			

Guidance Information

- 1 Entry into live work is conditional on the trainee meeting the minimum requirements of NZECP 46:2003: New Zealand Electrical Code of Practice for High Voltage Live Line Work available at https://worksafe.govt.nz/laws-and-regulations/standards/electricity-standards-and-codes-of-practice/.
- Evidence presented for assessment against this unit standard must be consistent with safe working practices and be in accordance with applicable legislative and industry requirements.
- Legislation, regulations and/or industry standards relevant to this unit standard include but are not limited to the current version of the Health and Safety at Work Act 2015; Electricity Act 1992; Electricity (Safety) Regulations 2010; and any subsequent amendments and replacements; Electricity supply industry codes of practice and documented enterprise procedures, including Safety Manual Electricity Industry (SM-EI) (2015) Wellington: Electricity Engineers' Association available at www.eea.co.nz.

4 Definitions

- Asset owner refers to a participant who owns or operates assets used for generating or conveying electricity.
- Industry requirements include all asset owner requirements; manufacturers' specifications; and enterprise requirements which may include the documented workplace policies, procedures, specifications, business, and quality management requirements relevant to the workplace in which assessment is carried out.
- 5 This unit standard includes but is not limited to conductors, insulators, cross arms, fittings and other components on poles, towers, other structures.
- It is recommended people achieve Unit 10529, Dismantle electricity network lines and structures; Unit 10538, Inspect, test, and clean live line tools and equipment; Unit 10542, Demonstrate knowledge of live line theory and procedures; or

demonstrate equivalent knowledge and skills, before being assessed against this unit standard.

Outcomes and performance criteria

Outcome 1

Replace and install hardware on structures using live line glove and barrier procedures up to 33kV.

Performance criteria

1.1 Worksite is prepared, and a safe working zone is established.

Range includes – site information, plans, procedures, approvals, tools, equipment, working platforms, communication with affected personnel.

1.2 Conductors are displaced and reinstated on intermediate structures and termination structures.

Range includes but is not limited to – auxiliary arms, cranes, mobile elevating work platforms, 2x2 block and tackles, hoists, strain sticks.

1.3 Hardware is replaced and installed.

Range includes – insulators, cross arms, fittings.

1.4 Completed work is reported concisely, in the required format and within the scheduled time frame, and existing records are updated.

Planned review date	31 December 2025
---------------------	------------------

Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment	
Registration	1	19 June 1997	31 December 2022	
Review	2	27 April 2001	31 December 2022	
Review	3	22 October 2003	31 December 2022	
Review	4	18 September 2009	31 December 2022	
Revision	5	21 May 2010	31 December 2022	
Review	6	27 February 2020	N/A	

Consent and Moderation Requirements (CMR) reference	0120
---	------

This CMR can be accessed at http://www.nzqa.govt.nz/framework/search/index.do.

Comments on this unit standard

Please contact Connexis – Infrastructure Industry Training Organisation qualifications@connexis.org.nz if you wish to suggest changes to the content of this unit standard.