

<b>Title</b>	<b>Installing and maintain traffic signs and delineators</b>		
<b>Level</b>	<b>3</b>	<b>Credits</b>	<b>8</b>

<b>Purpose</b>	People credited with this unit standard are able to: install and maintain traffic signs and delineators, and clear the worksite on completion of work.
----------------	--

<b>Classification</b>	Infrastructure Works > Infrastructure Civil Works
-----------------------	---

<b>Available grade</b>	Achieved
------------------------	----------

---

### Guidance Information

- 1 The following legislation and regulations must be complied with: Health and Safety in Employment Act 1992; and Health and Safety in Employment Regulations 1995.
- 2 Assessment against this unit standard must take place in a workplace environment. Assessment parameters will depend on company and site specific equipment, procedures, and practices. Practices must reflect industry best practice and comply with legislative requirements.
- 3 Definitions  
*Company requirements* include the policy, procedures, and methodologies of the company. They include legislative and regulatory requirements applicable to the company or a specific site. Requirements are documented in the company’s health and safety plans, traffic management plans, contract work programmes, quality assurance programmes, policies, and procedural documents.  
*Contract specifications* include plans, diagrams, and special technical conditions. They do not include special administrative conditions.

---

### Outcomes and performance criteria

#### Outcome 1

Install and maintain traffic signs and delineators.

#### Performance criteria

- 1.1 Traffic signs are set out and installed in accordance with contract specifications.  
 Range signs – advisory, regulatory, directional, informational;  
 installation – height, spacing, distance.
- 1.2 Traffic signs and components are maintained in accordance with contract specifications.

- 1.3 Delineators are installed in accordance with contract specifications.
- Range delineators – edge marker post, chevron, sight-board, guardrail, bridge-end marker, culvert marker, hazard markers; materials – timber, plastic, reflectorised, impact collapsible.
- 1.4 Traffic signs are cleaned in accordance with contract specifications.
- Range water hose, brushes, cloths, detergents, solvents.

**Outcome 2**

Clear the worksite on completion of work.

**Performance criteria**

- 2.1 Surplus and loose materials are cleared from the site in accordance with company requirements.
- 2.2 Temporary traffic control measures are removed in accordance with company requirements.

<b>Replacement information</b>	This unit standard, unit standard 22289, unit standard 22993, and unit standard 28712 were replaced by unit standard 31482.
--------------------------------	---

**This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.**

**Status information and last date for assessment for superseded versions**

Process	Version	Date	Last Date for Assessment
Registration	1	23 July 1997	31 December 2014
Review	2	25 September 2006	31 December 2016
Review	3	19 February 2015	31 December 2021
Review	4	27 September 2018	31 December 2021

<b>Consent and Moderation Requirements (CMR) reference</b>	0101
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.