

Title	Take control of an emergency at an infrastructure worksite		
Level	4	Credits	6

Purpose	People credited with this unit standard are able to take control of an emergency at an infrastructure works site.
----------------	---

Classification	Infrastructure Works > Generic Infrastructure Works
-----------------------	---

Available grade	Achieved
------------------------	----------

Guidance Information

- 1 Evidence presented for assessment against this unit standard must be consistent with safe working practices and be in accordance with relevant legislative and industry requirements.
- 2 Legislation relevant to this unit standard include: Health and Safety at Work Act 2015; and all subsequent amendments and replacements.
- 3 Definition
Industry requirements refer to relevant policies, processes, methodologies, industry codes of practice, site specific health and safety plans, standard operating procedures, site safety plans, quality plans, work plans, traffic management plans, contract work programmes, job safety analysis, safe work method statements, job instructions, manufacturer's requirements, contract specifications, manuals, procedural documents, Waka Kotahi New Zealand Transport Agency specifications and guidelines.
- 4 The range for this unit standard is evidence of three simulated or real emergencies.

Outcomes and performance criteria

Outcome 1

Take control of an emergency at an infrastructure works site.

Performance criteria

- 1.1 Emergency is assessed in accordance with site safety plan.
- 1.2 Communication channels to coordinate and control an emergency event are established and maintained in accordance with the site safety plan.
- 1.3 Critical actions and steps taken to control the emergency are consistent with the size and nature of the emergency and in accordance with the site safety plan.

- 1.4 At an accident, work is stopped safely, victim is attended to, area is secured, hazard is reassessed, and controls are put in place before work recommences.
- 1.5 In a case of serious harm, accident scene is not disturbed except to save life, limit suffering, maintain access to essential service or utility, or prevent serious damage or loss of property.
- 1.6 Site is reinstated in accordance with the site safety plan.
- 1.7 Documentation is completed and processed in accordance with the site safety plan.

Planned review date	31 December 2026
----------------------------	------------------

Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	27 October 2004	31 December 2016
Review	2	19 February 2015	31 December 2021
Review	3	30 August 2018	31 December 2023
Review	4	28 October 2021	N/A

Consent and Moderation Requirements (CMR) reference	0101
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.

Comments on this unit standard

Please contact Connexis - Infrastructure Industry Training Organisation qualifications@connexis.org.nz if you wish to suggest changes to the content of this unit standard.