

Title	Install traffic service poles, signage, and roadside furniture		
Level	3	Credits	4

Purpose	People credited with this unit standard are able to prepare for and carry out the installation of traffic service poles, signage, and roadside furniture.
----------------	---

Classification	Infrastructure Works > Road Construction
-----------------------	--

Available grade	Achieved
------------------------	----------

Guidance Information

- 1 The following legislation and regulations must be complied with: Health and Safety in Employment Act 1992; and Health and Safety in Employment Regulations 1995.
- 2 Assessment against this unit standard must take place in a workplace environment. Assessment parameters will be dependent on company and site specific equipment, procedures, and practices. Practices must reflect industry best practice and comply with legislative requirements.
- 3 This unit standard covers the installation of structures in the road reserve. It does not include mounting gantries on overhead structures, which is covered in unit standard 28712, *Mount a gantry sign*.
- 4 Definitions
As-built refers to what is actually constructed as opposed to that which was planned.
Company requirements include the policy, procedures, and methodologies of the company. They include legislative and regulatory requirements applicable to the company or a specific site. Requirements are documented in the company's health and safety plans, traffic management plans, contract work programmes, quality assurance programmes, policies, and procedural documents.
Contract specifications include plans, diagrams, and special technical conditions. They do not include special administrative conditions.

Outcomes and performance criteria

Outcome 1

Prepare for the installation of traffic service poles, signage, and roadside furniture.

Performance criteria

- 1.1 Locations of proposed fixtures are confirmed in accordance with contract specifications.

- 1.2 Locations of existing services are identified and marked in accordance with service authority plans and records.
- 1.3 Plant and equipment are confirmed in accordance with contract specifications and company requirements.

Outcome 2

Install traffic service poles, signage, and roadside furniture.

Range three of – regulatory signs, advisory signs, roadside furniture, hydrant markers.

Performance criteria

- 2.1 Foundations are excavated and installed in accordance with contract specifications.
- 2.2 Traffic service poles, signage, and roadside furniture are erected in accordance with contract specifications.
- 2.3 Locations of erected items and services are recorded on as-built plans in accordance with contract specifications.

Replacement information	This unit standard, unit standard 11316, unit standard 22993, and unit standard 28712 were replaced by unit standard 31482.
--------------------------------	---

This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.

Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	25 September 2006	31 December 2016
Review	2	19 February 2015	31 December 2021
Review	3	27 September 2018	31 December 2021

Consent and Moderation Requirements (CMR) reference	0101
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.