

| | | | |
|--------------|---|----------------|-----------|
| Title | Install exterior and interior, and wet area joinery and fixtures on site | | |
| Level | 3 | Credits | 10 |

| | |
|----------------|---|
| Purpose | People credited with this unit standard are able to: install exterior and interior joinery units; receive, install and protect interior stairs; install wet area joinery and fixtures; and complete work operations; on site. |
|----------------|---|

| | |
|-----------------------|---------------------------------|
| Classification | Construction Trades > Carpentry |
|-----------------------|---------------------------------|

| | |
|------------------------|----------|
| Available grade | Achieved |
|------------------------|----------|

Guidance Information

1 Definitions

Plant is used as in the Health and Safety in Employment Act 1992 to mean appliances, equipment, fittings, furniture, implements, machines, machinery, tools, vehicles, plus parts, controls, and anything connected.

Site documents refer to any official documentation for the site, and may include consents, working drawings, plans and specifications, reports, producer statements, any relevant industry standards, or any other documentation critical to the construction process.

Stair units for the purpose of this unit standard, include hand rails.

Work site practice refers to the documented procedures specific to a work site which set out the standard and required practices of that work site.

- 2 For outcome 4 of this unit standard, the installation of tubs, vanities, baths and showers includes only the installation of the units, and does not include the installation of plumbing pipework, including waste systems and potable water supply, and installation of valves, mixers or taps.
- 3 For all *on site* unit standards the practical assessment evidence must be provided in the context of commercial business construction operations, in the workplace, under normal workplace conditions.
- 4 Credit for this unit standard indicates compliance with industry practice. *Industry practice* refers to the ability to demonstrate knowledge and skills that reflect the productivity, uniformity, finish quality and material economies currently accepted within industry.

- 5 Legislation relevant to this unit standard includes:
Health and Safety in Employment Act 1992 and Health and Safety in Employment Regulations 1995;
Building Act 2004;
Resource Management Act 1991;
New Zealand Building Code.

Outcomes and performance criteria

Outcome 1

Install exterior joinery on site.

Performance criteria

- 1.1 Opening and frame or unit sizes are confirmed for accuracy in accordance with site documents.
- 1.2 Window and door frames are prepared and installed plumb and level with all packing, provision for air seal made, and fixed, in accordance with site documents and manufacturer's instructions.
- 1.3 Exterior finishing trim is installed to give a weather tight finish to the interface between building elements in accordance with site documents and manufacturer's instructions.

Range two of – scribes, facings, plugs, weather bar, sealant.

Outcome 2

Install interior joinery units on site.

Performance criteria

- 2.1 Interior joinery units are prepared and fixed in position, and are plumb, in line and level, in accordance with site documents.
- 2.2 Interior doors and frames are installed in accordance with site documents and manufacturer's instructions.
- 2.3 Timber and other trim is cut, fitted and fixed in accordance with site documents.
- 2.4 Temporary protection for all joinery units is provided in accordance with work site practice.

Outcome 3

Receive, install and protect interior stairs on site.

Performance criteria

- 3.1 Stair units are received and stored without damage in accordance with work site practice.
- 3.2 Stair units are trimmed and installed in accordance with site documents.
- 3.3 Temporary protection for all stair units is provided in accordance with work site practice.

Outcome 4

Install wet area joinery and fixtures on site.

Range two of – tub, vanity, bath, shower.

Performance criteria

- 4.1 Wet area joinery units are prepared and fixed to wall or floor, and are plumb and to line and level, in accordance with site documents.
- 4.2 Joints are waterproofed for wet area installations in accordance with site documents and manufacturer’s instructions.
- 4.3 Timber and other trim is cut, fitted and fixed in accordance with site documents.
- 4.4 Temporary protection for all wet area joinery units is provided in accordance with work site practice.

Outcome 5

Complete work operations on site.

Performance criteria

- 5.1 All operations are safely completed; workplace, tools, plant and equipment are cleaned; and tools, plant and equipment are stored in accordance with work site practice.

| | |
|--------------------------------|--|
| Replacement information | <p>This unit standard replaced unit standard 13055.</p> <p>This unit standard was replaced by unit standard 32442 and unit standard 32500.</p> |
|--------------------------------|--|

This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.

Status information and last date for assessment for superseded versions

| Process | Version | Date | Last Date for Assessment |
|--------------|---------|-------------------|--------------------------|
| Registration | 1 | 25 January 2008 | 31 December 2023 |
| Review | 2 | 30 September 2021 | 31 December 2023 |

| | |
|--|------|
| Consent and Moderation Requirements (CMR) reference | 0048 |
|--|------|

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.

This unit standard is expiring