

Title	Manufacture prestressed concrete flooring units		
Level	3	Credits	25

Purpose	<p>People credited with this unit standard are able to: prepare, set up prestressing equipment, moulds and storage areas, carry out the pre-pour process, place and test concrete, and finish concrete; for prestressed concrete flooring unit manufacture; and cure, destress and demould, lift and store, carry out post-pour checks and remedial work, and carry out delivery processes; for prestressed concrete flooring units; and complete work operations.</p>
----------------	--

Classification	Concrete > Precast Concrete
-----------------------	-----------------------------

Available grade	Achieved
------------------------	----------

Guidance Information

1 Definitions

Specifications refers to documented instructions (oral, written, graphic) and may include any of the following – manufacturer’s specifications, recommendations or technical data sheets; material specifications; specifications from a specialist source such as an architect, designer, engineer or a supervisor; site or work specific requirements.

Workplace practice refers to the documented procedures specific to a workplace which set out the standard and required practices of that workplace.

2 Credit for this unit standard indicates compliance with industry practice. *Industry practice* refers to the ability to demonstrate knowledge and skills that reflect the productivity, uniformity, finish quality and material economies currently accepted within industry.

3 Legislation and publications relevant to this unit standard include: Health and Safety in Employment Act 1992 and Health and Safety in Employment Regulations 1995; Building Act 2004;

NZS 3109:1997 *Concrete construction*, and NZS 3114:1987 *Specification for concrete surface finishes*, available from Standards New Zealand

(<http://www.standards.co.nz>).

Approved Code of Practice for the Safe Handling, Transportation and Erection of Pre-cast Concrete, available from Department of Labour

(<http://www.osh.dol.govt.nz/order/catalogue/pdf/concrete-ac.pdf>).

Outcomes and performance criteria

Outcome 1

Prepare to manufacture prestressed concrete flooring units.

Performance criteria

- 1.1 Job requirements for manufacture of prestressed concrete flooring units are identified in accordance with specifications and shop drawings.
- 1.2 Job requirements for manufacture of prestressed concrete flooring units are identified in accordance with production programme, including timeframe of job in relation to rate of manufacture and available labour hours.
- 1.3 Tools and equipment for manufacture of prestressed concrete flooring units are selected in accordance with job requirements.
- 1.4 Casting area for manufacture of prestressed concrete flooring units is selected in accordance with job requirements.
- Range considerations – size of work area needed, where units will be stored and/or stockpiled, safety in and around moulds, environmental factors, other work operations.
- 1.5 Strand for manufacture of prestressed concrete flooring units is selected in accordance with job requirements and specifications.
- Range verification of certification, size, grade.

Outcome 2

Set up prestressing equipment, moulds and storage areas for prestressed concrete flooring unit manufacture.

Performance criteria

- 2.1 Prestressing equipment for manufacture of prestressed concrete flooring units is set up in accordance with job requirements, specifications and workplace practice.
- 2.2 Mould for prestressed concrete flooring units is set up in accordance with job requirements, specifications and workplace practice.
- 2.3 Area for manufacture and storage of prestressed concrete flooring units is set up in accordance with job requirements, specifications and workplace practice.

Outcome 3

Carry out the pre-pour process for prestressed concrete flooring unit manufacture.

Performance criteria

- 3.1 The pre-pour process for prestressed concrete flooring units is carried out in accordance with job specifications and workplace practice.

Range identification of strand type and size, identification of reinforcing type and size, gathering of materials, initial setup of mould, placement of strand in mould, initial placement of reinforcing in the mould, safety devices in place before stressing of strand, pre-loading of strand to specified tension, checking of strand pre-load extension lengths, full specified loading of strand, final check of strand extension lengths, lock off pre-stressing equipment, tying off reinforcing, placement of bar chairs on strand and reinforcing, final setup of mould, securing of remaining bar chairs, placement of cast in items, securing of final mould attachments, pre-pour quality assurance procedures.

Outcome 4

Place and test concrete for prestressed concrete flooring unit manufacture.

Performance criteria

- 4.1 Concrete for prestressed concrete flooring unit manufacture is placed in accordance with NZS 3109:1997, job requirements, specifications and workplace practice.

Range factors to consider – segregation, layers, screeding, continuity of supply, vibration method, protection of strand.

- 4.2 Concrete for prestressed concrete flooring unit manufacture is tested in accordance with NZS 3109:1997 and specifications.

Outcome 5

Finish concrete for prestressed concrete flooring unit manufacture.

Performance criteria

- 5.1 Prestressed concrete flooring units are finished in accordance with NZS 3114:1987 and workplace practice.

Range from NZS 3114:1987 – three of F series, two of U series.

Outcome 6

Cure, destress and demould prestressed concrete flooring units.

Performance criteria

6.1 Prestressed concrete flooring units are cured in accordance with NZS 3109:1997, specifications and workplace practice.

Range two different curing methods, including testing procedures related to the curing.

6.2 Prestressed concrete flooring units are destressed in accordance with job and prestressing equipment requirements, and workplace practice.

6.3 Prestressed concrete flooring units are demoulded in accordance with job requirements and workplace practice.

Outcome 7

Lift and store prestressed concrete flooring units.

Performance criteria

7.1 Prestressed concrete flooring units are lifted safely and in accordance with specifications and workplace practice and manufacturer's specifications.

Range equipment used, lifting techniques.

7.2 Prestressed concrete flooring units are stored in accordance with specifications and workplace practice.

Range factors to consider – area suitable for high loadings, height capacity, delivery sequence versus storage sequence, dunnage points, pre-cambre.

Outcome 8

Carry out post-pour checks and remedial work for prestressed concrete flooring units.

Performance criteria

8.1 Prestressed concrete flooring units are checked for possible defects in accordance with workplace practice.

Range method, documentation required.

8.2 Remedial work on defects in prestressed concrete flooring units is carried out in accordance with specifications and workplace practice.

Range three defects.

Outcome 9

Carry out delivery processes for prestressed concrete flooring units.

Performance criteria

9.1 Standard forms associated with delivering prestressed concrete flooring units are confirmed as completed in accordance with workplace practice.

9.2 Loading of prestressed concrete flooring units for delivery is carried out in accordance with specifications and workplace practice.

Range loading, placement of dunnage, securing load on vehicle.

Outcome 10

Complete work operations.

Performance criteria

10.1 All operations are safely completed, workplace and equipment are cleaned in accordance with workplace practice, including environmental safety requirements; and routine maintenance is carried out in accordance with workplace practice.

Replacement information	This unit standard, unit standard 26526, and unit standard 26528 replaced unit standard 12036.
--------------------------------	--

This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.

Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	20 August 2010	31 December 2023
Review	2	27 January 2022	31 December 2023

Consent and Moderation Requirements (CMR) reference	0048
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.