

<b>Title</b>	<b>Mount a sign gantry</b>		
<b>Level</b>	<b>3</b>	<b>Credits</b>	<b>5</b>

<b>Purpose</b>	People credited with this unit standard are able to prepare for and mount a sign gantry.
----------------	--

<b>Classification</b>	Infrastructure Works > Infrastructure Civil Works
-----------------------	---

<b>Available grade</b>	Achieved
------------------------	----------

---

### Guidance Information

- 1 The following legislation and regulations must be complied with: Health and Safety in Employment Act 1992; and Health and Safety in Employment Regulations 1995.
- 2 Assessment against this unit standard must take place in a workplace environment. Assessment parameters will depend on company and site specific equipment, procedures, and practices. Practices must reflect industry best practice and comply with legislative requirements.
- 3 Definitions  
*As-built* refers to what is actually constructed as opposed to that which was planned.  
*Company requirements* include the policy, procedures, and methodologies of the company. They include legislative and regulatory requirements applicable to the company or a specific site. Requirements are documented in the company's health and safety plans, traffic management plans, contract work programmes, quality assurance programmes, policies, and procedural documents.  
*Contract specifications* include plans, diagrams, and special technical conditions. They do not include special administrative conditions.  
*Gantry* means a traffic sign assembly in which signs are mounted on an overhead support.  
*Set-out* means to set out a site by survey method using pegs.

---

### Outcomes and performance criteria

#### Outcome 1

Prepare to mount a sign gantry.

#### Performance criteria

- 1.1 Location of proposed gantry is identified and marked in accordance with contract specifications.

- 1.2 Locations of existing services are identified and marked in accordance with service authority plans and records.
- 1.3 Plant and equipment are confirmed in accordance with contract specifications and company requirements.

**Outcome 2**

Mount a sign gantry.

**Performance criteria**

- 2.1 Fittings are installed in accordance with contract specifications.
- 2.2 Gantry is erected in accordance with contract specifications.
- 2.3 Locations of erected gantry are recorded on as-built plans in accordance with contract specifications.

<b>Replacement information</b>	This unit standard, unit standard 11316, unit standard 22993, and unit standard 22289 were replaced by unit standard 31482.
--------------------------------	---

**This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.**

**Status information and last date for assessment for superseded versions**

Process	Version	Date	Last Date for Assessment
Registration	1	19 February 2015	31 December 2021
Review	2	27 September 2018	31 December 2021

<b>Consent and Moderation Requirements (CMR) reference</b>	0101
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.