

<b>Title</b>	<b>Prepare moulds to cast, and cast fibrous plaster cornice</b>		
<b>Level</b>	<b>4</b>	<b>Credits</b>	<b>10</b>

<b>Purpose</b>	<p>This unit standard aligns with the <i>New Zealand Certificate in Fibrous Plaster Manufacture – Specifications</i>, developed on behalf of the fibrous plaster manufacture industry to specify the skills and knowledge required to achieve the New Zealand Certificate in Fibrous Plaster Manufacture (Level 4) with an optional strand in Specialist Models and Mould Making [Ref: 3062].</p> <p>This unit standard is intended for those working in the fibrous plaster manufacturing industry.</p> <p>People credited with this unit standard are able to prepare moulds to cast, and cast, fibrous plaster cornice to the level required of a commercially competent fibrous plaster manufacturer.</p>
----------------	---

<b>Classification</b>	Construction Trades > Fibrous Plaster
-----------------------	---------------------------------------

<b>Available grade</b>	Achieved
------------------------	----------

### Guidance Information

This unit standard is one of a family of standards that align with the *New Zealand Certificate in Fibrous Plaster Manufacture – Specifications* and should be read, interpreted and assessed in the context of those *Specifications* and the New Zealand Certificate in Fibrous Plaster Manufacture (Level 4) with an optional strand in Specialist Models and Mould Making [Ref: 3062].

The overarching level of performance for the family of unit standards is commercial competence.

Commercial competence requires a candidate to be capable of consistently performing the requirements of the unit specification:

- to current regulatory, industry and commercial standards
- within a commercially viable timeframe
- in commercial environments
- without supervision
- in different and unfamiliar contexts.

The sufficiency of evidence required to demonstrate commercial competence against this unit standard is determined within the context of the family of unit standards aligned to the *Specifications*.

The assessor must be confident that the candidate is capable of applying the skills and knowledge included in this skill specification to the level, scope and complexity required to support the achievement of related skills included in the *Specifications*.

Commercial competence can only be demonstrated, and must be assessed, in the workplace.

The assessment of commercial competence must be corroborated and confirmed by a person who has current expertise in the fibrous plaster manufacture trade and has had the opportunity to regularly observe the candidate in the workplace.

#### Reference

*New Zealand Certificate in Fibrous Plaster Manufacture – Specifications*, Waihangā Ara Rau, December 2015, available from <https://www.waihanganga.nz>.

---

## Skill specification and performance level guidance

### Skill specification

Prepare moulds to cast, and cast, fibrous plaster cornice.

**Know** Features of the different types of fibrous plaster cornice.

Features of cornice moulds.

How to prepare and use different types of moulds.

Methods of casting different types of fibrous plaster cornice.

Methods of storing and drying fibrous plaster cornice.

The ratios of ingredients for plaster gauges used in the manufacture of fibrous plaster cornice.

**Do** Prepare moulds to cast fibrous plaster cornice.

Cast fibrous plaster cornice.

Remove cornice from the mould.

Store green cornice to dry.

### Performance level guidance

Types of moulds include – fibreglass, timber, plaster, rubber, or a combination of these.

Features include – size, form, shape, pattern, formation of back and edges.

The quantity of fibrous plaster cornice required to be cast in any given day depends on the size, shape and complexity of the product; the availability, quality and set-up of tables and moulds; setting times appropriate to the product; and production requirements.

Casting includes – mixing and applying plaster gauges, adding reinforcement, forming the back and edges.

Green cornice refers to the freshly cast cornice yet to be dried.

---

<b>Planned review date</b>	31 December 2025
----------------------------	------------------

#### **Status information and last date for assessment for superseded versions**

<b>Process</b>	<b>Version</b>	<b>Date</b>	<b>Last Date for Assessment</b>
Registration	1	30 August 2018	N/A
Rollover	2	27 April 2023	N/A

<b>Consent and Moderation Requirements (CMR) reference</b>	0048
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.

#### **Comments on this unit standard**

Please contact Waihanga Ara Rau Construction and Infrastructure Workforce Development Council [qualifications@waihangaararau.nz](mailto:qualifications@waihangaararau.nz) if you wish to suggest changes to the content of this unit standard.