

Title	Clear slips from roads		
Level	4	Credits	3

Purpose	People credited with this unit standard are able to prepare to clear slips, and clear, slips from roads.
----------------	--

Classification	Infrastructure Works > Road Maintenance
-----------------------	---

Available grade	Achieved
------------------------	----------

Guidance Information

- 1 Legislation relevant to this unit standard includes:
Health and Safety at Work Act 2015;
Resource Management Act 1991;
Health and Safety in Employment Regulations 1995;
Territorial Authority guidelines.
- 2 Assessment against this unit standard must take place in a workplace environment. Assessment parameters depend on company and site-specific equipment, procedures, and practices. Practices must reflect industry best practice and comply with legislative requirements.
- 3 Definitions
Company requirements include the policy, procedures, and methodologies of the company. They include legislative and regulatory requirements which may apply across the company or to a specific site. Requirements are documented in the company's health and safety plans, traffic management plans, contract work programmes, quality assurance programmes, policies, and procedural documents.
Contract specifications include plans, diagrams, and special technical conditions. They do not include special administrative conditions.

Outcomes and performance criteria

Outcome 1

Prepare to clear slips from roads.

Performance criteria

- 1.1 Area to be cleared is identified and located, and method is selected and confirmed in accordance with contract specifications and company requirements.

- 1.2 Site conditions are checked and confirmed as safe for clearing of slip to take place.
- 1.3 Plant, equipment, and materials are selected in accordance with method to be employed and company requirements.
- 1.4 Site management and communication requirements are identified and confirmed as in place before commencement of work.
- Range site safety plan, environmental plan, traffic management plan.

Outcome 2

Clear slips from roads.

Performance criteria

- 2.1 Slipped material is cleared from roadway and loaded for transport in accordance with any instructions from a geotechnical engineer, contract specifications and company requirements.
- 2.2 Slipped material is transported and disposed of in accordance with contract specifications and company requirements.
- 2.3 If further rebuilding or retaining work is required, barriers and temporary traffic management are installed to ensure road is safely passable in the interim in accordance with contract specifications and company requirements.

Planned review date	31 December 2023
----------------------------	------------------

Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	27 September 2018	N/A

Consent and Moderation Requirements (CMR) reference	0101
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.

Comments on this unit standard

Please contact Connexis Infrastructure ITO qualifications@connexis.org.nz if you wish to suggest changes to the content of this unit standard.