

<b>Title</b>	<b>Overlay interior linings for marine interiors</b>		
<b>Level</b>	<b>4</b>	<b>Credits</b>	<b>5</b>

<b>Purpose</b>	People credited with this unit standard are able to: prepare to overlay; and overlay interior linings for marine interiors.
----------------	---

<b>Classification</b>	Boating Industries > Boatbuilding
-----------------------	-----------------------------------

<b>Available grade</b>	Achieved
------------------------	----------

---

## Guidance Information

### 1 Definitions

*Interior linings* refers to exotic timber veneer panels used to line marine interiors for bespoke applications such as saloon and companionway linings.

*Job specifications* refers to the standard requirements of the job being undertaken.

*Preparation* refers to inspection and verifications of bulkheads and headlining grounds, cutting of materials, and fitting.

*Workplace policies and procedures* refers to the documented procedures and policies providing guidelines of the tasks and activities carried out in the workplace. This typically includes relevant health and safety policies to manage risk in the workplace.

- 2 All work practices must meet recognised codes of practice and documented workplace policies and procedures for personal, product, and workplace health and safety, and must meet the obligations required under the Health and Safety at Work Act 2015 and Resource Management Act 1991, and any subsequent amendments.

---

## Outcomes and performance criteria

### Outcome 1

Prepare to overlay interior linings for marine interiors.

### Performance criteria

- 1.1 The bulkheads and headlining grounds, or substrates are inspected and verified as correct in accordance with workplace policies and procedures.

Range may include – specified centres, straightness, level, plumb, specified tolerances, bracing, structural elements.

- 1.2 Any inconsistencies are remedied in accordance with workplace policies and procedures.

- 1.3 Materials are prepared in accordance with job specification for marine interiors.

## Outcome 2

Overlay interior linings for marine interiors.

Range overlay interior linings with complexity that includes – joins, curve, straight sections.

## Performance criteria

- 2.1 Interior linings are overlaid in accordance with job specifications and workplace policies and procedures for marine interiors.
- 2.2 Finished interior linings are checked and remedial action is taken if required to ensure job specifications are met.

<b>Planned review date</b>	31 December 2024
----------------------------	------------------

## Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	22 August 2019	N/A

<b>Consent and Moderation Requirements (CMR) reference</b>	0136
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.

## Comments on this unit standard

Please contact the NZ Marine and Composites ITO [training@nzmarine.com](mailto:training@nzmarine.com) if you wish to suggest changes to the content of this unit standard.