

Title	Maintain the TTM worksite, install and remove a worksite, and undertake an inspection activity		
Level	3	Credits	10

Purpose	People credited with this unit standard are able to: <ul style="list-style-type: none">• maintain the worksite under temporary traffic management (TTM);• install and remove a worksite where all TTM equipment is out of the live lane; and• undertake an inspection activity.
----------------	---

Classification	Infrastructure Works > Temporary Traffic Management
-----------------------	---

Available grade	Achieved
------------------------	----------

Guidance Information

- 1 Learning and assessment for this unit standard must be in accordance with the following:
 - Health and Safety at Work Act 2015;
 - Resource Management Act 1991;
 - Land Transport Act 1998;
 - Land Transport Rule: Setting of Speed Limits 2017;
 - Land Transport (Road User) Rule 2004.
- 2 Definitions

Company requirements include the policy, procedures, and methodologies of the company. They include legislative and regulatory requirements that may apply across the company or to a specific worksite. Requirements are documented in the company health and safety plans, traffic management plans (TMPs), contract work programmes, quality plans, policies, and procedural documents.

TTM equipment refers to equipment specifically used for TTM, including worksite protection, and may include but is not limited to temporary signs, delineation devices, temporary road safety barriers, and rotating flashing beacons.

Worksite refers to the section of road defined at each end by advance warning and end of works signs.

Outcomes and performance criteria

Outcome 1

Maintain the worksite under TTM.

Performance criteria

- 1.1 TTM equipment for the worksite is maintained in accordance with company requirements.
- 1.2 TTM equipment is operated to control alternating traffic flows in accordance with company requirements.
- 1.3 Safe work practices for the maintenance of the worksite are followed in accordance with company requirements.
- 1.4 Static worksite is maintained in accordance with company requirements.
- 1.5 Communication techniques, including techniques to resolve conflict, are followed to ensure the safety of the TTM crew during worksite operations.
- 1.6 Documents for the worksite under TTM are completed in accordance with company requirements.
- 1.7 Pedestrian numbers and pedestrians with special requirements are monitored, and alternative access provisions are actioned in accordance with the TMP, and company requirements.

Outcome 2

Install and remove a worksite where TTM equipment is out of the live lane.

Performance criteria

- 2.1 The TMP is checked to ensure it is approved and fit for purpose.
- 2.2 Installation and removal of TTM at the worksite is completed in accordance with the procedures set out in the TMP and company requirements.
- 2.3 Safe work practices for the installation and removal of the TTM equipment for the worksite are followed in accordance with company requirements.
- 2.4 Provisions are made for unattended worksites under TTM in terms of ensuring road users can pass by or through.

Outcome 3

Undertake an inspection activity.

- 3.1 Inspection activity is completed in accordance with company requirements.

This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.

Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	24 October 2019	31 December 2020
Revision	2	24 September 2020	31 December 2026
Review	3	27 May 2021	31 December 2026
Revision	4	24 October 2024	31 December 2026
Review	5	12 December 2024	31 December 2026

Consent and Moderation Requirements (CMR) reference

0101

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.