Title	Cut, fit, and fix interior linings and trim under supervision		
Level	3	Credits	9

-	People credited with this standard can, under supervision:  cut, fit, and fix interior linings and trim; and,  clean and store tools, plant and equipment used to install interior linings and trim.
---	--

Classification	Construction trades > Carpentry

Available grade	Achieved
-----------------	----------

#### **Guidance Information**

## 1 Scope of practice

Working *under supervision* means the ability to work to construction workplace standards under the supervision of a commercially competent practitioner whose role is to ensure the completed construction meets industry and regulatory requirements. This standard does not recognise commercial competence.

#### 2 Assessment

This unit standard must be assessed under the supervision of a commercially competent practitioner in construction workplace conditions that reflect:

- current health, safety, industry, and workplace requirements; and
- industry requirements for commercially acceptable timeframes.

Evidence generated for assessment against this standard must be verified by a person who has current expertise in the building and construction trades and has had the opportunity to regularly observe the candidate in the workplace.

## 3 Range

Evidence generated for assessment against this standard must meet workplace and industry requirements specified in:

- documented worksite specifications, procedures, and practices;
- manufacturer recommendations, specifications, and technical data sheets;
- applicable specifications from other sources such as an architect, designer, engineer, or supervisor;
- applicable material safety data sheets;
- NZS 3604:2011 Timber Framed Buildings;
- the New Zealand Building Code;
- consents, working drawings, plans and specifications, reports, producer statements, relevant industry standards, other documentation critical to the construction process.

Evidence generated for assessment against this standard must reflect the requirements of:

- Building Act 2004;
- Health and Safety at Work Act 2015;
- Resource Management Act 1991;
- Building Regulations 1992;
- Building (Forms) Regulations 2004;
- Health and Safety in Employment Regulations 1995.
- 4 Reference

NZS 3604:2011 *Timber Framed Buildings*. Available from Standards NZ (<a href="http://www.standards.co.nz">http://www.standards.co.nz</a>).

# Outcomes and performance criteria

#### **Outcome 1**

Cut, fit, and fix interior linings and trim under supervision.

Range

interior linings include two of – pre-finished board, plywood, medium-density fibre board, fibre cement;

plasterboard linings include two of – standard, water resistant, fire resistant, impact resistant, bracing, sound control;

interior trim includes two of – architrave, cornice, skirting, corner and joint mouldings, dado, scotia.

## Performance criteria

1.1 Undertake pre-installation verification checks.

Range

wall and ceiling framing members fixed; insulation installed according to specification and site documentation; pipes, wires, and other in-built services and fixtures installed in the wall cavities; required systems tests completed; confirmation of Building Consent Authority pre-line inspection.

1.2 Receive and store materials.

Range

materials include – interior linings, interior trim, plasterboard

linings;

consignment details checked, stored without damage.

- 1.3 Cut, fit, and fix interior linings for a construction job.
- 1.4 Cut, fit, and fix plasterboard linings for a construction job.
- 1.5 Cut, fit, and fix interior trim for a construction job.

#### Outcome 2

Clean and store tools, plant, and equipment used to install interior linings and trim.

## Range

plant includes – any machinery, vehicle, vessel, aircraft, equipment (including personal protective equipment), appliance, container, implement, or tool; any component of any of those things; anything fitted or connected to any of those things;

personal protective equipment includes – anything used or worn by a person (including clothing) to minimise risks to the person's health and safety; air-supplied respiratory equipment.

#### Performance criteria

- 2.1 Clean workplace, tools, and plant used to install interior linings and trim.
- 2.2 Store tools and plant used to install interior linings and trim.

Replacement information	This unit standard replaced unit standard 13058.
Planned review date	31 December 2026

## Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	30 September 2021	N/A

This CMR can be accessed at http://www.nzga.govt.nz/framework/search/index.do.

### Comments on this unit standard

Please contact the Building and Construction Industry Training Organisation at <a href="mailto:national.office@bcito.org.nz">national.office@bcito.org.nz</a> if you wish to suggest changes to the content of this unit standard.