| Title | Construct and strike commercial falsework and formwork under supervision | | |
|-------|--------------------------------------------------------------------------|---------|----|
| Level | 3 | Credits | 13 |

| Purpose | People credited with this standard can: construct and strike falsework and formwork under supervision; and clean and store tools, plant and equipment used to construct falsework and formwork. |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

| Classification | Construction Trades > Carpentry |
|----------------|---------------------------------|
|----------------|---------------------------------|

| Available grade | Achieved |
|-----------------|----------|
|-----------------|----------|

Guidance Information

1 Scope of practice

Working *under supervision* means the ability to work to construction workplace standards under the supervision of a commercially competent practitioner whose role is to ensure the completed construction meets industry and regulatory requirements. This standard does not recognise commercial competence.

2 Assessment

This unit standard must be assessed under the supervision of a commercially competent practitioner in construction workplace conditions that reflect:

- · current health, safety, industry, and workplace requirements; and
- industry requirements for commercially acceptable timeframes.

Evidence generated for assessment against this standard must be verified by a person who has current expertise in the building and construction trades and has had the opportunity to regularly observe the candidate in the workplace.

3 Range

Commercial falsework and formwork for concrete construction includes – high wall, column, suspended beam.

Evidence generated for assessment against this standard must reflect workplace and industry requirements specified in:

- documented worksite specifications, procedures, and practices;
- manufacturer recommendations, specifications, and technical data sheets;
- applicable specifications from other sources such as an architect, designer, engineer, or supervisor;
- applicable material safety data sheets;
- NZS 3109:1997 Concrete construction;
- NZS 3124:1987 Specification for concrete construction for minor works;
- the New Zealand Building Code.

Evidence generated for assessment against this standard must reflect the requirements of:

- Building Act 2004
- Health and Safety at Work Act 2015
- Resource Management Act 1991
- Building Regulations 1992
- Building (Forms) Regulations 2004
- Health and Safety in Employment Regulations 1995.

4 References

NZS 3109:1997 *Concrete construction*. Available from Standards NZ (http://www.standards.co.nz).

NZS 3124:1987 *Specification for concrete construction for minor works*. Available from Standards NZ (http://www.standards.co.nz).

Outcomes and performance criteria

Outcome 1

Construct and strike commercial falsework and formwork under supervision.

Performance criteria

1.1 Set out and erect falsework and formwork for a construction job.

Range line, level, plumb, specified tolerances, release agents.

- 1.2 Brace falsework and formwork to prevent displacement during construction.
- 1.3 Tie formwork to specified tolerances.

Range tie system may include a proprietary system.

1.4 Strike formwork and falsework.

Range concrete set to specification;

without damaging - formwork, falsework, concrete, ready for

re-use.

Outcome 2

Clean and store tool, plant and equipment used to construct falsework and formwork.

Range

plant includes – any machinery, vehicle, vessel, aircraft, equipment (including personal protective equipment), appliance, container, implement, or tool; any component of any of those things; anything fitted or connected to any of those things;

personal protective equipment includes – anything used or worn by a person (including clothing) to minimise risks to the person's health and safety; air-supplied respiratory equipment.

Performance criteria

- 2.1 Clean workplace, tools, and plant used to construct falsework and formwork.
- 2.2 Store tools and plant used to construct falsework and formwork.

| Replacement information | This unit standard replaced unit standard 13065. |
|-------------------------|--------------------------------------------------|
| | |

| Planned review date | 31 December 2026 |
|---------------------|------------------|
|---------------------|------------------|

Status information and last date for assessment for superseded versions

| Process | Version | Date | Last Date for Assessment |
|--------------|---------|-------------------|--------------------------|
| Registration | 1 | 30 September 2021 | N/A |

| Consent and Moderation Requirements (CMR) reference | 0048 |
|-----------------------------------------------------|------|
|-----------------------------------------------------|------|

This CMR can be accessed at http://www.nzqa.govt.nz/framework/search/index.do.

Comments on this unit standard

Please contact the Building and Construction Industry Training Organisation at national.office@bcito.org.nz if you wish to suggest changes to the content of this unit standard.