| Title | Undertake demolition work under supervision | | |
|-------|---|---------|---|
| Level | 3 | Credits | 7 |

| Purpose | People credited with this standard can, under supervision: plan demolition work; undertake demolition work; and clean and store tools, plant, and equipment used to undertake demolition work. |
|---------|---|
|---------|---|

| Classification | Construction Trades > Carpentry |
|----------------|---------------------------------|
|----------------|---------------------------------|

| Available grade | Achieved |
|-----------------|----------|
|-----------------|----------|

Guidance Information

1 Scope of practice

Working *under supervision* means the ability to work to construction workplace standards under the supervision of a commercially competent practitioner whose role is to ensure the completed construction meets industry and regulatory requirements. This standard does not recognise commercial competence.

2 Assessment

This unit standard must be assessed under the supervision of a commercially competent practitioner in construction workplace conditions that reflect:

- current health, safety, industry, and workplace requirements; and
- industry requirements for commercially acceptable timeframes.

Evidence generated for assessment against this standard must be verified by a person who has current expertise in the building and construction trades and has had the opportunity to regularly observe the candidate in the workplace.

3 Range

Evidence generated for assessment against this standard must reflect workplace and industry requirements specified in:

- documented worksite specifications, procedures, and practices;
- manufacturer recommendations, specifications, and technical data sheets;
- applicable specifications from other sources such as an architect, designer, engineer, or supervisor;
- applicable material safety data sheets;
- Best Practice Guidelines for Demolition in New Zealand;
- NZS 1801:1997 Occupational protective helmets;
- NZS 6803:1999 Acoustics Construction noise;
- AS/NZS 2210.3:2009) Occupational protective footwear Specification for safety footwear;

- AS/NZS 1891.1:2007 Industrial fall-arrest systems and devices Part 1: Harnesses and ancillary equipment;
- The New Zealand Building Code.

Evidence generated for assessment against this standard must reflect the requirements of:

- Building Act 2004
- Health and Safety at Work Act 2015
- Hazardous Substances and New Organisms Act 1996
- Resource Management Act 1991
- Building Regulations 1992
- Building (Forms) Regulations 2004
- Health and Safety in Employment Regulations 1995.

4 References

New Zealand Demolition and Asbestos Association (2011), *Best Practice Guidelines for Demolition in New Zealand*. Available from https://www.nzdaa.com/demolition. Standards New Zealand. (1997). *Occupational protective helmets* (AS/NZS 1801:1997). Available from https://www.standards.govt.nz/.

Standards New Zealand. (1999). *Acoustics - Construction noise* (NZS 6803:1999). Retrieved from https://www.standards.govt.nz/.

Standards New Zealand. (2009). Occupational protective footwear - Specification for safety footwear (AS/NZS 2210.3:2009). Available from https://www.standards.govt.nz/.

Standards New Zealand. (2007). *Industrial fall-arrest systems and devices - Part 1: Harnesses and ancillary equipment* (AS/NZS 1891.1:2007). Available from https://www.standards.govt.nz/.

Outcomes and performance criteria

Outcome 1

Plan demolition work under supervision.

Performance criteria

- 1.1 Identify demolition work using site documentation.
- 1.2 Inspect the demolition work site.

Range existing services, structural components to be removed, personal and public safety, waste disposal, site access.

1.3 Prepare a demolition plan.

Outcome 2

Undertake demolition work under supervision.

Performance criteria

- 2.1 Establish support for structural components prior to demolition.
- 2.2 Protect structures to remain against damage.
- 2.3 Carry out demolition work according to the demolition plan.
- 2.4 Dispose of debris and waste according to the demolition plan.

Outcome 3

Clean and store tools, plant, and equipment used to undertake demolition work.

Range

plant includes – any machinery, vehicle, vessel, aircraft, equipment (including personal protective equipment), appliance, container, implement, or tool; any component of any of those things; anything fitted or connected to any of those things;

personal protective equipment includes – anything used or worn by a person (including clothing) to minimise risks to the person's health and safety; air-supplied respiratory equipment.

Performance criteria

- 3.1 Clean workplace, tools, and plant used to undertake demolition work.
- 3.2 Store tools and plant used to undertake demolition work.

| | Replacement information | This unit standard replaced unit standard 18727. |
|--|-------------------------|--|
|--|-------------------------|--|

| Planned review date | 31 December 2026 |
|---------------------|------------------|
|---------------------|------------------|

Status information and last date for assessment for superseded versions

| Process | Version | Date | Last Date for Assessment |
|--------------|---------|-------------------|--------------------------|
| Registration | 1 | 30 September 2021 | N/A |

| Consent and Moderation Re | quirements (CMR) re | ference | 0048 |
|----------------------------------|---------------------|---------|------|
| | | | |

This CMR can be accessed at http://www.nzqa.govt.nz/framework/search/index.do.

Comments on this unit standard

Please contact the Building and Construction Industry Training Organisation national.office@bcito.org.nz if you wish to suggest changes to the content of this unit standard.