

Title	Explain temporary works on an infrastructure worksite		
Level	4	Credits	5

Purpose	People credited with this unit standard are able to explain temporary works on an infrastructure worksite.
----------------	--

Classification	Infrastructure Works > Generic Infrastructure Works
-----------------------	---

Available grade	Achieved
------------------------	----------

Guidance Information

- 1 Evidence presented for assessment against this unit standard must be consistent with safe working practices and be in accordance with relevant legislative and industry requirements.
- 2 Legislation and references relevant to this unit standard include:
 - Health and Safety at Work Act 2015;
 - *Temporary Works Procedural Control: Good Practice Guideline* available from [Temporary Works Forum \(NZ\) – SESOC](#).
- 3 Definitions
Industry requirements may refer to but are not limited to relevant policies, processes, methodologies, industry codes of practice, site specific health and safety plans, standard operating procedures, site safety plans, quality plans, work plans, traffic management plans, contract work programmes, job safety analysis, safe work method statements, job instructions, manufacturer's requirements, contract specifications, manuals, procedural documents and Waka Kotahi New Zealand Transport Agency specifications and guidelines.
Temporary works refer to hoardings, fences, gates, working platforms, scaffolding, shored excavations, batters, and screens.

Outcomes and performance criteria

Outcome 1

Explain temporary works on an infrastructure worksite.

Performance criteria

- 1.1 The importance of the risk register for temporary works is explained in accordance with the *Temporary Works Procedural Control: Good Practice Guideline*.

- 1.2 The role of the temporary works coordinator and temporary works supervisor is explained in terms of the chosen worksite.
- 1.3 The importance of training personnel in temporary works is explained in terms of the requirements for competent staff.
- 1.4 The difference between formwork and falsework is explained in accordance with the *Temporary Works Procedural Control: Good Practice Guideline*.
- 1.5 The temporary works for a chosen worksite are explained in terms of fit for purpose, duration of use, risks, equipment monitoring and checks.
- 1.6 Worksite conditions that impact on the temporary works are explained in terms of safe use including access and egress requirements.
- 1.7 The consequences of failure of the temporary works are explained in terms of injury, time, and cost.
- 1.8 Cleaning and storage methods for the temporary works are explained in terms of ensuring they are ready to use.

Planned review date	31 December 2026
----------------------------	------------------

Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	29 July 2021	N/A

Consent and Moderation Requirements (CMR) reference	0101
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.

Comments on this unit standard

Please contact Connexis - Infrastructure Industry Training Organisation qualifications@connexis.org.nz if you wish to suggest changes to the content of this unit standard.