

Title	Construct suspended ceilings to special detail		
Level	3	Credits	6

Purpose	People credited with this unit standard are able to: set out for special suspended ceiling details; construct special details for suspended ceilings; and complete documentation and clean up after work is completed.
----------------	--

Classification	Construction Trades > Specialist Interiors
-----------------------	--

Available grade	Achieved
------------------------	----------

Guidance Information

1 Definition

Specifications refer to documented specifications and may include any of the following: drawings, project or job requirements, manufacturers' specifications, recommendations or instructions, material specifications.

Work site practices refer to the practices generally acknowledged by the industry as being acceptable when no specific work site is relevant or available and refers to the documented procedures specific to a work site which set out the standard and required practices of that work site.

Plant is used as in the Health and Safety in Employment Act 1992 to mean: appliances, equipment, fittings, furniture, implements, machines, machinery, tools, vehicles, plus parts, controls, and anything connected to such plant.

2 Credit for this unit standard can be achieved on site through a registered assessor, or in a simulated environment with an accredited training provider.

3 All work practices must comply with the following:

Health and Safety in Employment Act 1992;

Health and Safety in Employment Regulations 1995; Resource Management Act 1991;

Building Act 2004;

Approved Code of Practice for the Safe Erection and Use of Scaffolding (Department of Labour, Wellington, 1995) available at <http://www.osh.govt.nz>;

AS/NZS 2785:2000 *Suspended ceilings – Design and installation*, available at Standards NZ <http://www.standards.co.nz>;

New Zealand Building Code.

4 Recommended prerequisite: Unit 6155, *Install suspended ceilings on site*, or demonstrate equivalent knowledge and skills.

Outcomes and performance criteria

Outcome 1

Set out for special suspended ceiling details.

Performance criteria

- 1.1 Type of detail is identified from manufacturer's specifications.
- 1.2 Access is arranged and complies with the Health and Safety in Employment Regulations.
- 1.3 Work site measurements are confirmed in accordance with work site practice.
- 1.4 Working drawings are completed to comply with manufacturer's specifications.
- 1.5 Materials are accepted and stored to ensure specified quality is maintained, in accordance with work site practice.
- 1.6 Setting out is done in accordance with working drawings.
- 1.7 All operations are completed without damage to the work site, tools, or plant.

Outcome 2

Construct special details for suspended ceilings.

Performance criteria

- 2.1 Special details are constructed to conform to manufacturer's specifications.
Range light troughs, bulkheads, expansion joints.
- 2.2 Completed special suspended ceiling conforms to manufacturer's specifications.
- 2.3 All operations are completed without damage to the work site, tools, or plant.

Outcome 3

Complete documentation and clean up after work is completed.

Performance criteria

- 3.1 Tools and plant are maintained, cleaned, and stored in accordance with work site practice.
- 3.2 Waste material is disposed of and work site is cleaned in accordance with work site practice.
- 3.3 Job documentation is completed in accordance with work site practice.

This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.

Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	18 January 1996	31 December 2014
Revision	2	5 July 1999	31 December 2024
Review	3	29 August 2000	31 December 2024
Revision	4	18 May 2005	31 December 2024
Review	5	19 May 2006	31 December 2024
Review	6	26 May 2022	31 December 2024

Consent and Moderation Requirements (CMR) reference

0048

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.