

<b>Title</b>	<b>Build a straight brick wall with a return corner</b>		
<b>Level</b>	<b>2</b>	<b>Credits</b>	<b>12</b>

<b>Purpose</b>	People credited with this unit standard are able to: set up bricklaying work area; lay bricks to straight wall; and complete work operations.
----------------	---

<b>Classification</b>	Masonry > Brick and Block Laying
-----------------------	----------------------------------

<b>Available grade</b>	Achieved
------------------------	----------

### Guidance Information

- 1 To demonstrate competence, minimum dimensions of wall should be 1m x 3m x 1.2m high to include corner and return corner.
- 2 This unit standard must be assessed against on the basis of evidence of demonstrated performance in the workplace and/or situations that reflect the workplace environment.
- 3 Definitions
 

*Buttered* refers to putting mortar on the end of the brick where it butts up against the previous brick.

*Industry practice* refers to the expected standard required at the location in which credit for this standard is sought; such standards may be set down in: industry codes of practice, enterprise procedures, which refer to documented procedures specific to the enterprise which set out the standard business practice, and activities of that enterprise.

*Site safety plan* refers to the documented safety plan which is required by law to ensure compliance with the Health and Safety in Employment Act, 1992.

*Specifications* refer to any, or all of the following:  
 manufacturer's specifications and/or recommendations;  
 site and/or workplace specific requirements.

*Plant* refers to appliances, equipment, fittings, furniture, implements, machines, machinery, tools, vehicles, plus parts, controls, and anything connected to such plant.
- 4 New Zealand Standards and legislation relevant to this unit standard include the following:
  - NZS 4210:2001, *Masonry Construction: Materials and Workmanship*;
  - NZS 3604:1999, *Timber Framed Buildings*;
  - Health and Safety in Employment Act, 1992;
  - Resource Management Act, 1991.

---

## Outcomes and performance criteria

### Outcome 1

Set up bricklaying work area.

#### Performance criteria

- 1.1 Area where wall is to be erected is confirmed as being in accordance with the project plans and specifications.
- 1.2 Actions taken in the event that site is unsuitable for erection of wall are in accordance with industry practice and delegated authority.
- 1.3 Plant and materials are located in accordance with work flow.
- Range may include but is not limited to – accessibility, services, protection against weather.
- 1.4 Materials used are in accordance with the specifications.
- 1.5 Work is set out in accordance with gauge and the specifications.
- Range includes but is not limited to – bond type, cuts, broken bonds.
- 1.6 Work of other trades is protected prior to commencement of work and during work in accordance with industry practice.

### Outcome 2

Lay bricks to straight wall.

#### Performance criteria

- 2.1 Mortar is mixed in accordance with the specifications.
- 2.2 Mortar bed is spread to provide even coverage of brick in accordance with the specifications.
- 2.3 Brick is buttered to fully cover the brick.
- 2.4 First course is laid level, plumb and to line in accordance with the specifications.
- 2.5 Corner is built to plumb, level, and gauge in accordance with the specifications.
- 2.6 Bricks are laid in accordance with the specifications.
- 2.7 Pointing profile and pointing are completed in accordance with NZS 4210.
- 2.8 Job is left in clean and tidy condition in accordance with industry practice.

**Outcome 3**

Complete work operations.

**Performance criteria**

- 3.1 All operations are completed without damage to project, plant, staff or materials.
- 3.2 All activities comply with safety requirements set down in the site safety plan.
- 3.3 All plant is used, maintained, cleaned, and stored and work site left as specified in accordance with manufacturers, and/or legislative requirements.
- 3.4 All documentation is completed in accordance with industry practice.
- 3.5 Surplus materials are dealt with in accordance with industry practice and legislative requirements.

**This unit standard is expiring. Assessment against the standard must take place by the last date for assessment set out below.**

**Status information and last date for assessment for superseded versions**

Process	Version	Date	Last Date for Assessment
Registration	1	16 January 1997	31 December 2011
Revision	2	8 April 1999	31 December 2011
Review	3	21 September 2007	31 December 2011
Revision	4	21 July 2011	31 December 2024
Review	5	30 June 2022	31 December 2024

<b>Consent and Moderation Requirements (CMR) reference</b>	0048
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.