

Title	Maintain and disestablish temporary civil worksites		
Level	2	Credits	3

Purpose	People credited with this unit standard are able to: <ul style="list-style-type: none"> – undertake maintenance of the worksite; – remove temporary buildings and works; and – clean up the worksite.
----------------	--

Classification	Infrastructure Works > Infrastructure Civil Works
-----------------------	---

Available grade	Achieved
------------------------	----------

Guidance Information

- 1 Evidence presented for assessment against this unit standard must be consistent with safe working practices and be in accordance with relevant legislative and industry requirements. Work on gas, telecommunications and power services should be carried out under supervision of the relevant service provider.
- 2 Legislation relevant to this unit standard includes:
 - Health and Safety at Work Act 2015;
 - Resource Management Act 1991;
 and all subsequent amendments and replacements.
- 3 Definition
Industry requirements refer to relevant policies, processes, methodologies, industry codes of practice, site specific health and safety plans, standard operating procedures, site safety plans, quality plans, work plans, traffic management plans, contract work programmes, job safety analysis, safe work method statements, job instructions, manufacturer's requirements, contract specifications, manuals, procedural documents, Waka Kotahi New Zealand Transport Agency specifications and guidelines.

Outcomes and performance criteria

Outcome 1

Undertake maintenance of the worksite.

Performance criteria

- 1.1 Gates, barricades, and fencing are maintained.
- 1.2 Worksite grounds are maintained in accordance with contract specifications.

1.3 Services are maintained in accordance with service provider requirements.

Range water, electricity, telephone, sewer and/or septic storage, stormwater.

1.4 Worksite buildings, accessories, and ablutions are maintained.

1.5 Storage facilities are maintained.

Outcome 2

Remove temporary buildings and works.

Performance criteria

2.1 Equipment and accessories are removed.

2.2 Services on the worksite are disconnected in accordance with service provider requirements.

2.3 Temporary constructions are dismantled and removed.

2.4 Temporary drains and sumps are disconnected and filled in accordance with service provider requirements.

Outcome 3

Clean up the worksite.

Performance criteria

3.1 Waste and unwanted materials are cleared and removed from the worksite in accordance with contract specifications.

3.2 Tools and equipment are cleaned, maintained, and transported away from the worksite.

3.3 Site area is restored to its specified condition in accordance with contract specifications.

Planned review date	31 December 2026
----------------------------	------------------

Status information and last date for assessment for superseded versions

Process	Version	Date	Last Date for Assessment
Registration	1	30 July 1996	31 December 2023
Review	2	9 March 1999	31 December 2023
Review	3	30 May 2000	31 December 2023

Process	Version	Date	Last Date for Assessment
Revision	4	25 September 2006	31 December 2023
Review	5	28 October 2021	N/A

Consent and Moderation Requirements (CMR) reference	0101
--	------

This CMR can be accessed at <http://www.nzqa.govt.nz/framework/search/index.do>.

Comments on this unit standard

Please contact Connexis - Infrastructure Industry Training Organisation qualifications@connexis.org.nz if you wish to suggest changes to the content of this unit standard.